

## PERFORMANCE SPECIFICATION

### CONNECTORS, COAXIAL, RADIOFREQUENCY, GENERAL SPECIFICATION FOR

This specification is approved for use by all Departments and Agencies of the Department of Defense

#### 1. SCOPE

1.1 Scope. This specification covers the general requirements and tests for radiofrequency connectors used with flexible RF cables and certain other types of coaxial transmission lines.

1.2 Classification. Connectors shall be of the following classes, categories, and PIN's, as specified (see 3.1).

1.2.1 Class. The class of connectors shall consist of the following:

- a. Class 1 - A class 1 connector is a connector which is intended to provide superior RF performance at specified frequencies, and for which all RF characteristics are completely defined.
- b. Class 2 - A class 2 connector is intended to provide mechanical connection within an RF circuit providing specified RF performance.

1.2.2 Categories. The categories of connectors shall be designated by an A (field serviceable), B (non-field replaceable), C (field replaceable solder center contact), D (field replaceable crimp center contact) and E (field replaceable), as follows:


- a. Category A - Connectors which do not require special tools to assemble shall be designated as category A connectors. Standard wrenches, soldering equipment, pliers, etc., are not defined as special tools.
- b. Category B - Connectors which require special tools to assemble shall be designated as category B connectors. These connectors may be used for original installations only. Field replacement is intended to be made by categories A, C, D, E, or F connectors which shall provide the same form, fit and function. Category B connectors will not be stocked or procured by the Government.
- c. Category C - Connectors which require only standard military crimping tools and standard cable stripping dimensions to assemble shall be designated as category C connectors. The standard military crimping tool shall be as specified (see 3.1).
- d. Category D - Connectors which require only standard military crimp tools for the center contact and outer ferrule, and standard cable stripping dimensions to assemble shall be designated as category D connectors. The standard military crimp tools shall be as specified (see 3.1).
- e. Category E - Connectors using semi-rigid cables with standard stripping dimensions and using standard military tools. The method of assembly of the connector to the cable outer conductor shall be by solder.
- f. Category F - Connectors using semirigid cables with standard stripping dimensions and using standard military assembly tools. The method of assembly of the connector to the cable shall be solderless.

Beneficial comments, recommendations, additions, deletions, clarifications, etc., and any data which may improve this document should be sent to: Defense Electronics Supply Center, ATTN DESC-ELD1, 1507 Wilmington Pike, Dayton OH 45444-5765, or telephone (513) 296-5391, or facsimile (FAX) (513) 296 8868.

MIL-PRF-39012D

1.2.3 Part or identifying number (PIN) The PIN shall consist of the letter "M" followed by the basic specification sheet number, and a sequentially assigned four digit dash number. The first digit in the dash number designates the material of the connector body (shell); i.e., "0" for brass, "3" for corrosion-resistant steel, or "4" for copper beryllium.

Example:



The "-" designates a standard military part. This position, when filled with the letter 'B' (i.e., M39012/01BXXXX), signifies a military part which is for OEM use only. The part is assembled to the cable with special tooling. Acquisition of this type part by any agency other than OEM's is prohibited and will result in the substitution of the equivalent military replacement part (i.e., if "M39012/01BXXXX" is submitted for acquisition, "M39012/01-XXXX" will be recommended).

## 2 APPLICABLE DOCUMENTS

2.1 Government specifications and standards. Unless otherwise specified, the following specifications and standards, of the issue listed in that issue of the Department of Defense Index of Specifications and Standards specified in the solicitation, form a part of this specification to the extent specified herein.

### SPECIFICATIONS

#### FEDERAL

- QQ-W-290 - Nickel Plating (Electrodeposited).
- QQ-P-35 - Passivation Treatment For Corrosion Resistant Steel.
- QQ-S-365 - Silver Plating, Electrodeposited, General Requirements For.
- QQ-S-763 - Steel Bars, Wire, Shapes and Forgings, Corrosion-Resisting.
- WW-T-799 - Tube, Copper, Seamless, Water and Refrigeration (For use with Solder Flared - or Compression Type Fittings)
- ZZ-R-765 - Rubber, Silicone.

#### MILITARY

- MIL-I-17214 - Indicator, Permeability Low-Mu (Go-No-Go).
- MIL-G-45204 - Gold Plating, Electrodeposited.

(See supplement 1 for applicable specification sheets.)

### STANDARD

#### FEDERAL

- FED-STD-H28 - Screw-Thread Standards for Federal Services

#### MILITARY

- MIL-STD-130 - Identification Marking of U.S. Military Property.
- MIL-STD-202 - Test Methods for Electronic and Electrical Component Parts.
- MIL-STD-348 - Radio Frequency Connector Interfaces
- MIL-STD-889 - Dissimilar Metals.
- MIL-STD-1344 - Test Methods for Electrical Connectors.
- MS20995 - Wire, Safety or Lock

(Copies of specifications, standard, handbooks, drawings, and publications required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.2 Other publications. The following document(s) form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DoD adopted shall be the issue listed in the current DoDISS and are supplement thereto, if applicable

#### AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

- ASTM A484 - General Requirement for Stainless and Heat-Resisting Wrought Steel Product (except wire).
- ASTM A582 - Free-Machining Stainless and Heat-Resisting Steel Bars, Hot-Rolled or Cold-Finished
- ASTM B16 - Free-Cutting Brass Rod, Bar and Shapes for Use in Screw Machines
- ASTM B36 - Brass Plate, Sheet, Strip and Rolled Bar.
- ASTM B121 - Leaded Brass Plate, Sheet, Strip and Rolled Bar
- ASTM B124 - Copper and Copper Alloy Forging Rod, Bar and Shapes.
- ASTM B139 - Phosphor Bronze Rod, Bar and Shapes.
- ASTM B152 - Copper Sheet, Strip, Plate and Rolled Bar.
- ASTM B194 - Copper Beryllium Alloy Plate, Sheet, Strip and Rolled Bar.
- ASTM B196 - Copper Beryllium Alloy Rod and Bar.
- ASTM B197 - Copper Beryllium Alloy Wire.
- ASTM D1457 - Polytetrafluoroethylene (PTFE) Molding and Extrusion Materials
- ASTM D2116 - FEP Fluorocarbon Molding and Extrusion Materials."

(Application for copies of ASTM publications should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, Pennsylvania 19103.)

#### AMERICAN NATIONAL STANDARDS INSTITUTE, INC.

ANSI B46.1-1962 - Surface Texture.

(Application for copies should be addressed to the American National Standards Institute, Inc., 1430 Broadway, New York, NY 10018.)

#### INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS, INC.

IEEE Standard 287 - Standard for Precision Coaxial Connectors.

(Application for copies should be addressed to the Institute of Electrical and Electronic Engineers, Inc., 345 East 47th Street, New York, NY 10017.)

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using federal agencies.)

### 3. REQUIREMENTS

3.1 Specification sheets. The individual item requirements shall be as specified herein and in accordance with the applicable specification sheets. In the event of any conflict between requirements of this specification and the specification sheets, unless specifically stated otherwise herein, the specification sheets shall govern.

3.2 Qualification. Connectors furnished under this specification shall be products which are qualified for listing on the applicable qualified products list at the time set for opening of bids (see 4.4 and 6.3). Permission to grant qualification testing on category "B" connectors shall only be granted when a noncategory "B" connector is available on the latest issue of the Qualified Products List.

3.3 Critical interface material. Material shall be as specified herein and in table 1. If materials other than those specified are used, the contractor shall certify to the qualifying activity that the substitute material enables the connectors to meet the requirements of this specification. Acceptance or approval of any constituent material shall not be construed as a guaranty of the acceptance of the product. When a definite material is not specified, a material shall be used which will enable the connector to meet the requirements of this specification.

TABLE I. Materials.

Component material	Applicable specification
Phosphor bronze .....	ASTM B139
Soft copper .....	ASTM B152
Copper .....	MW-T-799
PTFE fluorocarbon .....	ASTM D1457
FEP fluorocarbon .....	ASTM D2116
Silicon rubber .....	ZZ-R-765

**3.3.1 Critical interface materials and finish.** Unless otherwise specified (see 3.1), connector center contacts and bodies shall be plated in the following manner in order to meet the requirements of this specification and avoid detrimental interactions between dissimilar metals.

**3.3.1.1 Center contacts.** Center contacts shall be gold plated to a minimum thickness of 0.000050 inch in accordance with MIL-G-45204, type II, class 1 over a 0.000050 inch minimum nickel underplate in accordance with QQ-N-290, class 1. Plating of the internal surfaces of the contact shall be of sufficient thickness to ensure the intended performance of the contact is met and is to be uniform in appearance. A silver underplate shall not be permitted. ¶

NOTE: No PIN changes will be made as a result of this plating change. The change will be tracked via the manufacturer's date code.

**Disposition of stock.** Manufacturers and their selling agents and distributors may ship from stock connectors which were manufactured and qualified to the previous amendment (5) until 11 December 1995.

**3.3.1.2 Connector bodies.** All brass bodied connectors shall be silver plated in accordance with QQ-S-365 to a minimum thickness of 0.000200 inch over a copper underplate. All copper beryllium bodied connectors shall be gold plated in accordance with MIL-G-45204, type II, class 1 over a copper flash. All corrosion resistant steel bodied connectors shall be passivated in accordance with QQ-P-35, unless otherwise specified (see 3.1). NOTE: Ferrous or nickel alloys shall not be used on brass or copper beryllium bodied connectors (i.e., coupling nuts, etc.). ¶

**3.3.2 Dissimilar metals.** Dissimilar metals between which an electromotive couple may exist shall not be placed in contact with each other. Reference is made to MIL-STD-889 for definition of dissimilar metals.

**3.3.3 Nonmagnetic materials.** All parts (except hermetic sealed connectors) shall be made from materials which are classed as nonmagnetic (see 3.8).

**3.3.4 Spring members.** Unless otherwise specified (see 3.1), center contact spring members shall be made of copper beryllium.

**3.4 Configuration and features.** Connectors shall be of the configuration and physical dimensions specified (see 3.1). On class I connectors (see 1.2.1) each half of a connector pair must be separately optimized in VSWR (see 4.7.12). It is not permitted to compensate for discontinuities of one connector by the design of the mating connector.

**3.4.1 Mating (visual indication).** When applicable (see 3.1), a visual means shall be provided to indicate when two mating connectors are properly mated.

**3.4.2 Screw threads.** Screw threads shall be in accordance with FED-STD-H28 unless otherwise specified (see 3.1).

**3.4.3 Connector interfaces.** Connector interfaces shall be in accordance with MIL-STD-348 unless otherwise specified (see 3.1)

¶ Past experience has shown that these plating conditions allow these connectors to meet the performance requirements of this specification. Other plating and material options may be permitted with the approval of the preparing and qualifying activities.

### 3.5 Force to engage/disengage.

3.5.1 Bayonet and threaded types. When tested as specified in 4.7.2.1, the torque necessary to completely couple or uncouple the connectors shall not exceed that specified (see 3.1). Also the longitudinal force necessary to initiate the engaging or disengaging cycle shall not exceed that specified (see 3.1).

3.5.2 "Push on" connector types. When tested as specified in 4.7.2.2, the forces necessary to fully engage or disengage the connectors shall not exceed that specified (see 3.1).

3.6 Coupling proof torque. When tested as specified in 4.7.3, the coupling mechanism (threaded types) shall not be dislodged, and the connector shall meet requirements of 3.5.1. The interface dimensions of the connector shall remain as specified (see 3.1).

3.7 Mating characteristics. When connectors are tested as specified in 4.7.4, the mating dimensions shall be gauged as specified (see 3.1) and the dimensions shall remain within the specified tolerances (see 3.1).

3.8 Permeability of nonmagnetic materials. When connectors (except hermetic sealed) are tested as specified in 4.7.5, the permeability ( $\mu$ ) shall be less than 2.0.

3.9 Hermetic seal (pressurized connectors). When connectors are tested as specified in 4.7.6, the leakage rate shall not exceed that specified (see 3.1).

3.10 Leakage (pressurized connectors). When connectors are tested as specified in 4.7.7, there shall be no leakage as detected by escaping air bubbles.

3.11 Insulation resistance. When connectors are tested as specified in 4.7.8, the insulation resistance shall not be less than that specified (see 3.1).

3.12 Center contact retention. When all class I connectors, and class II where applicable (see 3.1) are tested as specified in 4.7.9, the center contacts must not be displaced from the specified interface dimensions in the uncabled connector by the application of the specified axial force (see 3.1) in either direction.

3.13 Corrosion. When connectors are tested as specified in 4.7.10, there shall be no exposure of the base metal on the interface or mating surface, and they shall meet the requirements of 3.5.1 or 3.5.2 as applicable.

3.14 Voltage standing wave ratio (VSWR). When connectors are tested as specified in 4.7.11, the VSWR shall not exceed that specified over the frequency range specified (see 3.1).

3.15 Connector durability. When connectors are tested as specified in 4.7.12, they shall show no evidence of severe mechanical damage and the coupling device shall remain functional. Connectors shall meet the applicable requirements of 3.5 and 3.7.

3.16 Contact resistance. When connectors are tested as specified in 4.7.13, the contact resistance of the center contact, outer contact, and braid to connector shall be as specified (see 3.1). The following statement takes precedence over any specification sheet interpretation; The outer contact resistance values given for steel bodied connectors are typical values and are for engineering information purposes only.

3.17 Dielectric withstanding voltage. When connectors are tested as specified in 4.7.14, there shall be no evidence of breakdown.

3.18 Vibration. When the cabled (or wired, as applicable) connector is tested as specified in 4.7.15, there shall be no electrical interruptions exceeding 1 microsecond ( $\mu$ s), or as otherwise specified (see 3.1). There shall be no evidence of visual mechanical damage after the test, and the contact resistance of the center contact shall not be changed by more than the specified amount (see 3.1 and 3.16).

3.19 Shock (specified pulse) When the cabled (or wired, as applicable) connector is tested as specified in 4.7.16, there shall be no electrical interruptions exceeding 1  $\mu$ s unless otherwise specified (3.1). There shall be no evidence of visual or mechanical damage after the test, and the contact resistance of the center contact shall not be changed by more than the specified amount (see 3.1).

3.20 Thermal shock. After testing as specified in 4.7.17, there shall be no evidence of visual mechanical damage to the connector and it shall meet the dielectric withstanding voltage requirement (see 3.17), and the contact resistance specified for the center contact shall not be exceeded (see 3.16).

3.21 Moisture resistance. When connectors are tested as specified in 4.7.18, there shall be no evidence of damage. They shall withstand the dielectric withstanding voltage specified (see 3.17), and the insulation resistance shall not be less than that specified (see 3.11).

3.22 Corona level. When connectors are tested as specified in 4.7.19, at the altitude and voltage specified (see 3.1), there shall be no evidence of sustained corona discharge.

3.23 RF high potential withstanding voltage. When connectors are tested as specified in 4.7.20, there shall be no breakdown, or the leakage current specified shall not be exceeded (see 3.1).

3.24 Cable retention force. When connectors are tested as specified in 4.7.21, there shall be no evidence of mechanical failure, loosening, rupture, or discontinuity. The direct clamping of the cable jacket shall not be the primary method of cable retention.

3.25 Coupling mechanism retention force. When tested as specified in 4.7.22, the coupling mechanism shall not be dislodged from the connector and shall be capable of meeting the requirements of 3.5.1 immediately after the test.

3.26 RF leakage. When connectors are tested as specified in 4.7.23, the total leakage, cable to cable shall not exceed that specified (see 3.1).

3.27 RF insertion loss. When connectors are tested as specified in 4.7.24, the insertion loss shall not exceed that specified (see 3.1).

3.28 Assembly instructions. Complete assembly instructions shall be furnished by the vendor with each connector procured under this specification. It is not the intention of this specification to require assembly instructions with uncabled connectors (i.e., solder pot, solder tab or posts, etc.). Assembly instructions shall include:

- (a) Cable preparation - stripping dimensions and tolerances.
- (b) List and description of crimping or special tools if required (see 1.2.2).
- (c) Pictorial presentation of sub-assemblies and loose piece parts
- (d) Sufficient pertinent dimensions for verification of correct parts; as a minimum the cable entry openings for conductor, dielectric, braid, and jacket shall be specified.
- (e) Recommended cable clamp tightening torque (if applicable).
- (f) Military PIN and manufacturer's PIN.

3.29 Marking. Connectors and associated fittings shall be permanently and legibly marked in accordance with the general marking requirements of MIL-STD-130 with the military PIN (see 1.2.3), manufacturer's federal supply code, and final assembly date code. The marking location is optional; when practicable, a location should be picked that will be least likely to be covered in cable assembly or installation. Marking is required on all parts manufactured to this specification unless specifically excepted (see 3.1).

3.30 Workmanship. Connectors and associated fittings shall be processed in such a manner as to be uniform in quality and shall be free from sharp edges, burrs and other defects that will affect life, serviceability or appearance.

3.31 Manufacturers' control drawing. Connector manufacturers shall insure that special tooling and dies are documented. The replacement category A, C, D, E, or F PIN's shall be listed on the manufacturers' control drawing.

3.32 Safety wire hole pullout. When applicable (see 3.1), connectors are to be tested as specified in 4.7.25. There shall be no evidence of hole tear out.

#### 4. VERIFICATION

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items shall meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to accept defective material.

4.1.2 Test equipment and inspection facilities. Test and measuring equipment and inspection facilities of sufficient accuracy, quality, and quantity to permit performance of the required inspection shall be established and maintained by the contractor. The establishment and maintenance of a calibration system to control the accuracy of the measuring and test equipment shall be required.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

- a. Qualification inspection (see 4.4).
- b. ~~Conformance inspection (see 4.5).~~
- c. ~~Periodic inspection (see 4.6).~~

4.3 Inspection conditions. Unless otherwise specified, all inspections shall be performed in accordance with the test conditions specified in the "GENERAL REQUIREMENTS" of MIL-STD-202 or MIL-STD-1344. For each test of threaded coupling connectors, where the test is performed on mated pairs, the pair shall be torqued to the specified value (see 3.1).

4.4 Qualification inspection. Qualification inspection shall be performed at a laboratory acceptable to the Government (see 6.3) on sample units produced with equipment and procedures normally used in production.

4.4.1 Sample size. Thirty class 1 connectors of the same PIN, or eighteen class 2 connectors of the same PIN with its mating connector (see 1.2.1), shall be subjected to qualification inspection.

4.4.2 Group qualification. For group qualification of all series of connectors covered by this specification, see 3.1. Group qualification will be limited to those connectors for which evidence of manufacturing capability is demonstrated by providing engineering drawings to the qualifying agency. The Government reserves the right to authorize performance of any or all qualification inspection of additional types in the group that are considered necessary for qualification within each group.

4.4.3 Inspection routine. The sample shall be subjected to the inspections specified in table II. All sample units shall be subjected to the inspection of group 1. The sample units shall then be divided equally into six groups of 5 units (class 1) or three units each (class 2) and subjected to the inspection for their particular group and in the sequence given for that group.

4.4.4 Failures. One or more failures shall be cause for refusal to grant qualification approval.

4.4.5 Retention of qualification. To retain qualification, the contractor shall verify in coordination with the qualifying activity the capability of manufacturing products which meet the performance requirements of this specification. Refer to the qualifying activity for the guidelines necessary to retain qualification to this particular specification. The contractor shall immediately notify the qualifying activity at any time that the inspection data indicates failure of the qualified product to meet the performance requirements of this specification.

TABLE II. Qualification inspection.

Examination or test	Requirement paragraph	Test method paragraph
<u>Group I</u>		
Visual and mechanical examination		
Material	3.3	
Finish	3.3.1	4.7.1.1
Dissimilar metals	3.3.2	
<del>Configuration and features (dimensions)</del>	3.4	4.7.1.2
Marking	3.29	
Mating (visual indication)	3.4.2	4.7.1.1
Force to engage/disengage		
Bayonet and threaded types	3.5.1	4.7.2.1
Push-on connector types	3.5.2	4.7.2.2
Coupling proof torque	3.6	4.7.3
Mating characteristics	3.7	4.7.4
Permeability of nonmagnetic materials	3.8	4.7.5
Workmanship	3.30	4.7.1
Hermetic seal (pressurized connectors only)	3.9	4.7.6
Leakage (pressurized connectors only)	3.10	4.7.7
Insulation resistance	3.11	4.7.8
<u>Group II</u>		
Center contact retention	3.12	4.7.9
Corrosion	3.13	4.7.10
<u>Group III</u>		
Voltage standing wave ratio	3.14	4.7.11
Connector durability	3.15	4.7.12
Safety wire hole pullout	3.32	4.7.25
<u>Group IV</u>		
Center contact resistance	3.16	4.7.13
Dielectric withstanding voltage	3.17	4.7.14
Vibration <sup>1/</sup>	3.18	4.7.15
Shock (specified pulse) <sup>1/</sup>	3.19	4.7.16
Thermal shock	3.20	4.7.17
Moisture resistance	3.21	4.7.18
Corona level <sup>1/</sup>	3.22	4.7.19
RF high potential withstanding voltage <sup>1/</sup>	3.23	4.7.20
Cable retention force	3.24	4.7.21
Coupling mechanism retention force	3.25	4.7.22
<u>Group V</u>		
RF leakage <sup>1/</sup>	3.26	4.7.23
<u>Group VI</u>		
RF insertion loss <sup>1/</sup>	3.27	4.7.24
<u>Group VII</u>		
Contact resistance	3.16	4.7.13

<sup>1/</sup> These tests to be performed only during initial qualification as long as the qualifying design and manufacturing process has not been changed

4.5 Conformance inspection.

4.5.1 Inspection of product for delivery. Inspection of product for delivery shall consist of groups A and B inspection.

4.5.1.1 Inspection lot. An inspection lot shall consist of all connectors of the same PIN produced under essentially the same conditions, and offered for inspection at one time

4.5.1.2 Group A inspection. Group A inspection shall consist of the inspections specified in table III in the order shown.

4.5.1.2.1 Sampling plan (group A). Table III tests shall be performed on a production lot basis. Samples shall be selected in accordance with table IV. If one or more defects are found, the lot shall be screened for that particular defect and defects removed. A new sample of parts shall be selected in accordance with table IV and all group A tests again performed. If one or more defects are found in the second sample, the lot shall be rejected and shall not be supplied to this specification.

TABLE III. Group A inspection.

Inspection	Requirement paragraph	Test method paragraph	Sampling procedure
Visual and mechanical examination			
Material	3.3		See table IV
Finish <sup>1/</sup>	3.3.1		
Dissimilar metals	3.3.2		
Configuration and features	3.4	4.7.1 1	
Marking	3.29		
Workmanship	3.30		
Mating (visual indication)	3 4.1		
Dielectric Withstanding voltage	3.17	4.7.14	
Hermetic seal (pressurized connectors only)	3.9	4.7.6	
Leakage (pressurized connectors only)	3.10	4.7.7	

<sup>1/</sup> Verification of finish may be accomplished using the manufacturer's process controls providing these controls are clearly equal to or more stringent than the requirements of this specification.

4.5.1.2.2 Visual inspection (group A inspection). Each connector shall be visually examined for completeness, workmanship, and identification requirements. Attention shall be given to those assemblies that require a gasket to determine the condition of the gasket. Gaskets missing, twisted, buckled, kinked, or damaged in any way shall be cause for rejection.

TABLE IV. Inspection level.

Lot size	Visual and mechanical inspection	
	Major	Minor 1/
1 to 8	All	5
9 to 15	All	5
16 to 25	20	5
26 to 50	20	5
51 to 90	20	7
91 to 150	20	11
151 to 280	20	13
281 to 500	47	16
501 to 1,200	47	19
1,201 to 3,200	53	23
3,201 to 10,000	68	29
10,001 to 35,000	77	35
35,001 to 150,000	96	40
150,001 to 500,000	119	40
500,001 and over	143	40

1/ Samples may be pulled from either the production lot itself or from samples pulled from the lot for major defect testing.

## NOTES

1. Major defect: A major defect is a defect, other than critical, that is likely to result in failure, or to reduce materially the usability of the unit of product for its intended purpose.
2. Minor defect: A minor defect is a defect that is not likely to reduce materially the usability of the unit of product for its intended purpose, or is a departure from established standards having little bearing on the effective use or operation of the unit.
3. Critical defect: A critical defect is a defect that judgment and experience indicate is likely to result in hazardous or unsafe conditions for individuals using, maintaining, or depending upon the product; or a defect that judgment and experience indicate is likely to prevent performance of the tactical function of a major end item such as a ship, aircraft, tank, missile, or space vehicle.

4.5.1.3 Group B inspection. Group B inspection shall consist of the inspections specified in table V in the order shown, and shall be made on sample units which have been subjected to and passed the group A inspection. Connectors having identical piece parts may be combined for lot purposes and shall be in proportion to the quantity of each PIN numbered adapter produced.

4.5.1.3.1 Group B sampling plan. A sample of parts shall be randomly selected in accordance with table VI. If one or more defects are found, the lot shall be screened for that particular defect and defects removed. After screening and removal of defects, a new sample of parts shall be randomly selected and subjected to all tests in accordance with table V. If one or more defects are found in the second sample, the lot shall be rejected and shall not be supplied to this specification.

TABLE V. Group B inspection.

Inspection	Requirement paragraph	Test method paragraph
Force to engage/disengage		
Bayonet and threaded type	3.5.1	4.7.2.1
Push-on connector type	3.5.2	4.7.2.2
Coupling proof torque	3.6	4.7.3
Mating characteristics	3.7	4.7.4
Permeability of nonmagnetic materials	3.8	4.7.5
Insulation resistance	3.11	4.7.8
Voltage standing wave ratio (cabled) <sup>1/</sup>	3.14	4.7.11

<sup>1/</sup> Destructive test. When a VSWR failure occurs the defect which caused the failure shall be determined and the entire lot shall be screened for that/those particular defects and defects removed. A new sample of parts shall be selected in accordance with table VI and all tests again performed.

TABLE VI. Inspection level.

Lot size	Sample size	VSWR sample size
1 to 8	5	1
9 to 15	5	1
16 to 25	5	2
26 to 50	5	2
51 to 90	5	3
91 to 150	11	3
151 to 280	13	3
281 to 500	16	3
501 to 1,200	19	5
1,201 to 3,200	23	5
3,201 to 10,000	29	5
10,001 to 35,000	35	5
35,001 to 150,000	40	8
150,001 to 500,000	40	8
500,001 and over	40	8

4.5.1.3.2 Disposition of sample units. Sample units which have passed all the group B inspection may be delivered on the contract or purchase order, if the lot is accepted. Any connector deformed or otherwise damaged during testing shall not be delivered on the contract or order.

4.6 Periodic inspection. Periodic inspection shall consist of group C. Except where the results of these inspections shown noncompliance with the applicable requirements (see 4.6.1.4), delivery of products which have passed groups A and B shall not be delayed pending the results of these periodic inspections.

4.6.1 Group C inspection. Group C inspection shall consist of the inspections specified in table VII, in the order shown. Group C inspection shall be made on sample units selected from inspection lots which have passed the groups A and B inspection.

4.6.1.1 Sampling plan. Twelve sample units of the same PIN shall be selected from the first lot produced after the date of notification of qualification. Thereafter, twelve sample units of the same PIN shall be selected from current production after 200,000 connectors have been produced, or not less than once every 3 years, whichever occurs first. The sample units shall be divided equally and subjected to the inspections of the six subgroups.

4.6.1.2 Failures. If one or more sample units fails to pass group C inspection, the lot shall be considered to have failed.

4.6.1.3 Disposition of sample units. Sample units which have been subjected to group C inspection shall not be delivered on the contract or order.

4.6.1.4 Noncompliance. If a sample fails to pass group C inspection, the manufacturer shall notify the qualifying activity and the cognizant inspection activity of such failure and take corrective action on the materials or processes, or both, as warranted, and on all units of product which can be corrected and which are manufactured under essentially the same materials and processes, and which are considered subjected to the same failure. Acceptance and shipment of the product shall be discontinued until corrective action, acceptable to the qualifying activity has been taken. After the corrective action has been taken, group C inspection shall be repeated on additional sample units (all tests and examinations, or the test which the original sample failed, at the option of the qualifying activity). Groups A and B inspections may be reinstated, however, final acceptance and shipment shall be withheld until the group C inspection has shown that the corrective action was successful. In the event of failure after reinspection, information concerning the failure shall be furnished to the cognizant inspection activity and the qualifying activity

TABLE VII. Group C inspection.

Inspection	Requirement paragraph	Test method paragraph
Subgroup 1		
Center contact retention	3.12	4.7.9
Corrosion	3.13	4.7.10
Subgroup 2		
Voltage standing wave ratio (cabled)	3.14	4.7.11
Connector durability	3.15	4.7.12
Safety wire hole pullout	3.32	4.7.25
Subgroup 3		
Center contact resistance	3.16	4.7.13
Vibration <sup>1/</sup>	3.18	4.7.15
Shock (specified pulse) <sup>1/</sup>	3.19	4.7.16
Thermal Shock	3.20	4.7.17
Moisture resistance	3.21	4.7.18
Corona level <sup>1/</sup>	3.22	4.7.19
RF high potential withstanding voltage <sup>1/</sup>	3.23	4.7.20
Cable retention forces	3.24	4.7.21
Coupling mechanism retention force	3.25	4.7.22
Subgroup 4		
RF leakage <sup>1/</sup>	3.26	4.7.23
Subgroup 5		
RF insertion loss <sup>1/</sup>	3.27	4.7.24
Subgroup 6		
Contact resistance	3.16	4.7.13

<sup>1/</sup> These tests to be performed only during initial qualification as long as the qualifying design and manufacturing process has not been changed

#### 4.7 Methods of inspection.

4.7.1 Test methods. The following identified tests and test methods assure connector integrity within typical operating conditions and applications. Alternate commercial industry standard test methods are allowed; however when an alternate method is used, the qualifying activity must be notified prior to the performance of the test. The test method described herein are proven methods and shall be the referee method in case of dispute.

4.7.1.1 Visual and mechanical examination. Connectors and associated fittings shall be examined to verify that the design, construction, physical dimensions, assembly instructions, marking and workmanship are in accordance with the applicable requirements (see 3.1, 3.3, 3.4, 3.28, 3.29, and 3.30).

4.7.1.2 Dimensional examination. Mating dimensions shall be examined by mating the connector with its applicable mating gauges or other suitable means acceptable to the Government.

NOTE: The documents listed in supplement 1 show the overall dimensions of the connector when assembled to the appropriate cable, and the detail mating dimensions at the interface. No other dimensions or details will be shown. The cable-end construction and other dimensions are controlled by performance requirements of the specification, i.e., cable retention, VSWR, RF leakage, etc., with cable in place.

#### 4.7.2 Force to engage/disengage.

4.7.2.1 Bayonet and threaded types (see 3.5.1). The connector shall be engaged with its mating standard part (see 3.1). During the entire coupling/uncoupling cycle (until the connector is fully engaged/disengaged) the forces and/or torques necessary shall not exceed those specified (see 3.1). A thread coupled connector is fully engaged with its mating standard part when their reference planes (see 3.1) coincide. A bayonet coupled connector is fully engaged with its mating standard part when the bayonet studs have passed the detent and their reference planes coincide. No additional tightening torque shall be applied. The mating standard part is a steel jig containing the critical interface dimensions finished to the tolerances specified (see 3.1). Its spring members when applicable shall be heat treated beryllium copper. The surface finish or mating surfaces shall be 16 microinches rms maximum, per ANSI B46.1-1962.

4.7.2.2 "Push-on" connector types (see 3.5.2). The connector under test shall be engaged with its standard mating part (gauge). During this engaging cycle the force necessary to fully engage the connectors shall not exceed that specified (see 3.1). Upon completion of engagement, an opposite force necessary for disengagement shall be applied. This force shall be within the limits specified, and shall include any unlatching forces required.

4.7.3 Coupling proof torque (see 3.6). The connector under test shall be engaged with its mating standard part (gauge) and the coupling nut tightened to the torque value specified (see 3.1). After one minute the connector under test and its mating standard part shall be disengaged.

4.7.4 Mating characteristics (see 3.7). After insertion of the specified oversize pin the specified number of times (see 3.1), the contact to be tested shall be held rigid by means of a suitable jig or fixture. A gauge containing the test pin or test ring and a suitable force indicating dial shall be aligned to within 0.004 IIR of any plane passing through the axis of the contact under test. Engagement or withdrawal of the test pin or test ring shall be made smoothly and at such a rate that the dial does not bounce or otherwise give a false reading. The test pin or test ring may be chamfered to facilitate entry, but the specified engagement length shall not include the chamfer length and the finish shall be as specified and in accordance with ANSI B46.1-1962.

4.7.5 Permeability of nonmagnetic materials (see 3.8). The permeability of the connector shall be measured with an indicator conforming to MIL-I-17214.

4.7.6 Hermetic seal (see 3.9). Connectors shall be tested in accordance with method 112, MIL-STD-202. The following details shall apply:

- a. Test condition letter: C.
- b. Procedure number: 1.
- c. Leakage rate sensitivity:  $10^{-8}$  cubic centimeters per second

4.7.7 Leakage (pressurized) (see 3.10). Connectors shall be subjected to air pressure specified (see 3.1) applied to one end, and the whole assembly immersed in water at a temperature of 15° to 25°C the connector shall remain immersed for at least 2 minutes.

4.7.8 Insulation resistance (see 3.11). Connectors without cables (when applicable) shall be tested in accordance with method 302, test condition B, MIL-STD-202. Measure between the center contact and body.

4.7.9 Center contact retention (see 3.12). An axial force (see 3.1) shall be applied, first in one direction and then the other, to the center contact of an assembled and uncabled connector utilizing a method and force measuring device suitable to the Government. The inner contact shall be inspected after the force has been applied in one direction and again after the force has been applied in the opposite direction to determine if the contact has been displaced from the specified interface dimensions.

4.7.10 Corrosion (see 3.13). Unmated and uncabled connectors shall be tested in accordance with method 101, MIL-STD-202. The following details and exceptions shall apply:

- a. Test condition letter: See 3.1.
- b. Salt solution: 5 percent.

After exposure, connectors shall be washed, shaken and lightly brushed as specified in method 101 of MIL-STD-202 and then permitted to dry for 24 hours at 40°C. Connectors shall then be examined for evidence of corrosion, pitting, and ease of coupling.

4.7.11 Voltage standing wave ratio (VSWR) (see 3.14). The VSWR shall be measured in accordance with the following procedure or a method acceptable to the Government. In the event of dispute the method outlined herein shall be used. Diagrams for the swept frequency VSWR system check out and measurement procedures are shown on figure 1.

In the basic measurement setup of figure 1, detector 1 provides a feedback signal to the swept RF source in order to normalized the output signal of detector 2. The frequency-amplitude characteristics of detectors 1 and 2 should be matched within .5 dB.

To measure VSWR several sweeps are made with the slotted line probe incrementally positioned over at least a half wave length at the lowest frequency of interest. In this manner an X-Y display is generated whose upper and lower envelope limits represent maximum and minimum amplitudes of the standing wave for each frequency in the test band. A base line may be generated by making a sweep with no input to the measurement channel amplifier. The resultant X-Y display is calibrated according to the characteristics of the measurement channel detector and amplifier, e.g., linear, square law, logarithmic, etc.


The VSWR test system is checked out by successively terminating the slotted line with the elements shown in steps 1 and 2 and sweeping the frequency over the specified test band (see 3.1). In step 1 the system VSWR shall be less than  $1.02 + .004 F$  ( $F$  measured in GHz). In step 2, the system VSWR shall be as specified (see 3.1).


For qualification and group C inspection (see tables II and VII), the system is checked out with the slotted line terminated as in step 3 using the specified cable (see 3.1). The impedance variation (random and/or periodic) from the nominal characteristic impedance specified for the selected test cable should be no more than 1.0 percent when tested by time domain reflectometry. In step 3, the system VSWR shall be as specified (see 3.1). For qualification and group C inspection, the connector under test is measured with the slotted line terminated as in step 4. The VSWR shall be as specified (3.1).

Group B inspection tests (see table V) are performed with the slotted line terminated as shown in step 7. The input part of the cable simulator must have the same interface configuration, dimensions, and dielectric as the recommended cable interface for the connector under test. The cable simulator for group B inspection tests must meet the specified VSWR (see 3.1) when tested as shown in step 6.


The standard precision adapter interface shall conform to IEEE Standard 287. Item 6 (standard precision adapters) shall not exceed the specified VSWR requirements (see 3.1). Standard test adapter designs shall be approved by the military qualifying agency.

4.7.12 Connector durability (see 3.15). Each connector under test shall be mated with a typical production connector in accordance with this specification. The connector shall be subjected to the number of cycles of mating and unmating specified (see 3.1). The connector and its mating part shall be completely engaged and completely disengaged during this cycle. Lubrication of the threads or rotational parts shall not be employed for this test unless specified (see 3.1). It is permissible to shake or blow debris from the threads or interface surfaces at intervals of not less than 50 cycles. Solvents or tools shall not be used for cleaning.



 PRECISION HERMAPHRODITIC CONNECTORS


STANDARD PRECISION ADAPTERS



LEGEND

FIGURE 1 Swept frequency VSWR test

MIL-PRF-39012D




- ① SWEPT RF SOURCE
- ② ISOLATING DEVICE
- ③ RF PROBE OR POWER DIVIDER
- ④ ISOLATING DEVICE
- ⑤ SLOTTED LINE WITH PRECISION HERMAPHRODITIC OUTPUT CONNECTOR RESIDUAL VSWR LESS THAN 1.006 + 0.03F (F IN GHz)
- ⑥ STANDARD PRECISION ADAPTER MAXIMUM VSWR (SEE 3.1)
- ⑦ CONNECTOR UNDER TEST
- ⑧ DETECTOR NO 2
- ⑨ AMPLIFIER
- ⑩ X-Y DISPLAY
- ⑪ DETECTOR NO 1
- ⑫ CABLE SIMULATOR TERMINATION
- ⑬ SELECTED TEST CABLE FOR GROUP C QUALIFICATION TESTS
- ⑭ PRECISION HERMAPHRODITIC CABLE CONNECTOR
- ⑮ PRECISION HERMAPHRODITIC TERMINATION
- ⑯ STANDARD PRECISION ADAPTERS
- ⑰ SELECTED LONG CABLE WHOSE ATTENUATION AT THE LOWEST TEST FREQUENCY IS 26 dB MINIMUM (SEE 3.1)

FIGURE 1 Swept frequency VSWR test - Continued

4.7.13 Contact resistance (see 3.16). All contact resistance tests shall be conducted with the apparatus shown in figure 2. Circuit adjustments and the measurement procedures for all contact resistance tests shall be in accordance with 4.7.13.1. The contact resistance to be measured are:

- The contact resistance between the cable braid or outer conductor and the connector at the point of contact.
- The contact resistance of the mated outer conductor contacts (the coupling nut must be removed for this measurement).
- The contact resistance of the mated inner conductor contacts.

4.7.13.1 General procedure. The apparatus shall be assembled as shown in figure 2. The contacts,  $C_1$  -  $C_2$ , shown in the figure represent the mating contacts upon which millivolt drop tests are to be conducted.



- Remove contacts  $C_1$  -  $C_2$  from the measuring circuit
- Close switch SW.
- Adjust  $R_2$  for a millivoltmeter (mVm) reading of 50 millivolts.
- Connect Contacts  $C_1$  -  $C_2$  to the measuring circuit and mate.
- Check to see that mVm drops significantly prior to opening switch in (f).
- Open switch SW.
- Adjust  $R_1$  for a circuit current (A) of one ampere.
- Measure the millivolt drop across contacts  $C_1$  -  $C_2$  and call this "e "
- Compute contact resistance Contact resistance (milliohms) = e millivolts - one ampere

FIGURE 2. Diagram for contact resistance

4.7.14 Dielectric withstanding voltage (see 3.17). Connectors shall be tested in accordance with method 301 of MIL-STD-202. The following details shall apply:

a. Special preparations or conditions.

- (1) The maximum relative humidity shall be 50 percent. When facilities are not available at this test condition, connectors shall be tested at room ambient relative humidity. In case of dispute, if the test has been made at room ambient relative humidity, retest shall be made at 50 percent maximum relative humidity.
- (2) The center contact of plug connectors and receptacle connectors shall be positioned in such a manner as to simulate actual assembly conditions.
- (3) Precautions shall be taken to prevent air-gap voltage breakdowns.
- (4) The voltage shall be metered on the high side of the transformer.

b. Magnitude of test voltage (see 3.1): The voltage shall be instantaneously applied.

c. Nature of potential: Alternating current.

d. Points of application of test voltage: Between the center contact and body.

4.7.15 Vibration (see 3.18). A complete connector assembly shall be mounted as shown on figure 3 and vibrated in accordance with test condition B, method 204, MIL-STD-202. The center and outer contacts shall be connected to a suitable monitoring device. Suitable coaxial cable or wire as applicable, using the normal connecting devices of the connector and clamped as shown in figure 3, shall be used. At least 100 milliamperes shall be flowing through each set of contacts. Contacts may be connected in series. The connector shall be mounted by its normal mounting device and engaged by its normal coupling device. No safety wire shall be used. Cable to cable connectors may be held to the jig of figure 3 by a suitable clamp on one half of the connector assembly. The following conditions shall apply:

a. Test condition letter (see 3.1).

b. Continuity shall be monitored during vibration with a detector capable of detecting interruptions of 1  $\mu$ s duration or longer, or as specified at 100 milliamperes.




FIGURE 3 Vibration testing set-up

**4.7.16 Shock (specified pulse) (see 3.19).** The connector shall be mated with its mating connector (see 3.1) and subjected to method 213 of MIL-STD-202. The following exceptions and details shall apply:

- a. Receptacles and panel or bulkhead mounted connectors and adapters shall be mounted by normal means. All other connectors and adapters shall be rigidly clamped to the vibration table.
- b. Acceleration requirements (see 3.1).
- c. Three blows in each of three mutually perpendicular planes; one of which shall be parallel to the axis of the connector.
- d. Continuity shall be monitored during shock as specified in 4.7 15(b)
- e. Center contact resistance shall be measured in accordance with 4.7.13 after the shock test.


**4.7.17 Thermal shock (see 3.20).** Connectors shall be subjected to method 107 of MIL-STD-202. The following details shall apply:

- a. Test condition letter (see 3.1).
- b. The contact resistance tests on the center contact shall be performed before and after the thermal shock test and examined for mechanical damage (see 3.1).

**4.7.18 Moisture resistance (see 3.21).** The connector shall be mated and cabled with its mating connector and shall be subjected to method 106, MIL-STD-202. The following exceptions and conditions shall apply:

- a. No initial measurements.
- b. No load.
- c. Step 7b (vibration) shall be omitted.
- d. Measurements shall be made at high humidity when specified (see 3.1).
- e. The connector shall withstand the dielectric withstanding voltage specified (see 2.6.14) after the drying period.

**4.7.19 Corona level (see 3.22).** The test sample shall be connected to a mating connector and arranged in a suitable test circuit such as indicated in figure 4. Components of the test circuit shall be corona free to the extent that a discharge of five picocoulombs or less can be measured when the 60 Hz test potential is increased to the value specified at the reduced pressure specified (see 3.1). The type of cable and length of cable used shall be as specified (see 3.1). No grease or similar compounds shall be used in or on the test item. After the sample is purged of air, the 60 Hz voltage shall be slowly increased until the detector, operated at a sensitivity of five picocoulombs, indicates a sustained corona discharge. The voltage shall then be decreased until corona is at the five picocoulombs level or less. The latter value is being the corona level of the connector under test. The contractor may, at his own option, use a corona detector (which has been approved by the Government) for performing the test in lieu of the test set up of figure 4.



- C - Corona free coupling capacitor (see note 1).
- D - Discharge display.
- L1 - Input line filter (see note 2).
- L2 - 10-50 kHz detector input filter.
- A - Detector amplifier.
- T1 - 0-130 V variable transformer.
- T2 - High voltage transformer (corona free - less than 5 picocoulombs).
- V - Voltmeter.

NOTES-

1. Equal to or greater than total circuit capacitance.
2. 100 dB 14 kHz to 10 GHz

FIGURE 4 Equipment and schematic for measuring corona level

4.7.20 RF high potential withstanding voltage (see 3.23). Connectors shall be mated with their mating connectors (see 3.1) and approximately 2 inches of their standard cable (see 3.1) appropriately attached. This assembly shall then be inserted into the high impedance circuit as shown in figure 5, or equivalent, and instantaneously subjected to the RF voltage and frequency specified (see 3.1) between the center contact and body of the connectors. The duration of the test shall be 1 minute. The RF voltage source shall be frequency stabilized and have an approximate pure sine wave output with minimum harmonic content. Means shall be provided to indicate disruptive discharge and leakage current. The maximum leakage current shall be as specified (see 3.1).




FIGURE 5. Circuit diagram for RF high potential withstanding voltage.

4.7.21 Cable retention force (see 3.24). When specified (see 3.1), the connector shall be assembled to its standard mating test cable. The connector shall be firmly fixed and a movable sleeve attached to the cable. The sleeve is then moved longitudinally away from the fixed connector gradually and in such a manner that the cable remains unbent and untwisted. A scale for measuring the retention force (see 3.1) shall be attached to the sleeve. The force shall be held for 30 seconds minimum. The assembly shall then be examined for mechanical failure, loosening, or rupture and tested for continuity using a suitable test method. When specified (see 3.1), a torque shall be applied to the cable about its axis in each direction relative to the connector at the location and to the torque value given on the detail specification sheet. The cable (flexible types only) shall then be bent at a radius of 10 times the diameter of the cable starting at the connectors at an angle of  $90^\circ \pm 5^\circ$  from the axis of the connector, then reversed  $180^\circ \pm 10^\circ$ . Repeat this procedure four times, then retest and reexamine as outlined above.

4.7.22 Coupling mechanism retention forces (see 3.25). The connector body and coupling mechanism shall be respectively secured to the lower and upper jaws of a tensile tester in an appropriate manner. A tensile load shall be applied at a rate of approximately 100 pounds/minute up to the force as specified and held at that value for one minute (see 3.1). During the one minute of steadily applied force, the coupling mechanism shall be rotated with respect to the connector body, two full revolutions in each direction.

4.7.23 RF leakage (see 3.26). The mating connector pair to be tested shall be assembled as shown on figure 6A and tested as shown on figure 6B. (The procedure for determining the dimensions of the cavity on figure 6B may be found in paragraph 30 of the appendix. The close fitting brass tubing shall be machined to thread into connector in lieu of compression nut (see 3.1). This test setup between 500 MHz and 11 GHz, shall have a dynamic range from -20 dBm to better than -100 dBm or a difference of 90 dB. Using +20 dBm RF source with 10 dB isolation, an additional 30 dB range can be obtained by use of attenuator pads or a step attenuator producing a total range of 120 dB. The shorting plunger is adjusted to produce a maximum reading in the detector with the triaxial assembly inserted. The insertion loss caused by the insertion of the triaxial assembly adjusted as shown in a measure of the total leakage of the mated connector pair both at its interface as well as at the clamping points to both cables.

Reference

"RF Leakage Characteristics of Popular Coaxial Cables and Connectors, 500 MS to 7.5 Gc", by J. Zorzy and RF Muehlberger, in the Microwave Journal, November 1961, pp 80-86.




FIGURE 6A. Connector assembly for RF leakage test.




FIGURE 6B. RF leakage test set-up

4.7.24 RF insertion loss (see 3.27). The connector shall be tested as shown on figure 7. Insertion loss of a mated connector pair is defined as the increase of a loss due to insertion of a mated connector pair in a cable; this includes the reflection losses to the cable and the dissipating losses in the pair. First insert cable assembly number 1 and tune out its input VSWR by means of tuner number 4 and balance setup. Then insert the cable assembly number 2 which includes the connector pair under test. With tuner number 4 in the same position and the electrical length of the cable assembly the same as that of number 1, record increase of insertion loss; add to this as a correction the cable loss of the removed section due to the length  $\Delta L_1 + \Delta L_2$  at this frequency. The sum of the increase and the correction is the insertion loss of the connector pair. Use of alternate test methods may be approved by the qualifying activity.




FIGURE 7 Method of insertion loss measurement of rated connector pair

4.7.25 Safety wire hole pullout (see 3.32). A single strand of safety wire shall be looped through the safety wire hole and secured to itself. Forces of 15 pounds (67 newtons) minimum shall be applied to the safety wire pulling away from the connector. One pull shall be parallel to the connector axis and one pull perpendicular to the connector axis (see figure 8). The safety wire shall be corrosion resistant steel .020 inch diameter (24 gauge) or .015 inch diameter, (27 gauge) in accordance with MS20995. This test is to be conducted under static conditions. All holes are to be tested individually.




FIGURE 8. Safety wire hole pullout procedure.

## 5. PACKAGING

5.1 Packaging requirements. The requirements for packaging shall be as specified in the contract or order.

## 6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. Connectors and fittings covered by this specification are intended for use in radiofrequency application up to the frequency specified (see 3.1).

6.2 Ordering data. Acquisition documents must specify the following:

- a. Title, number and date of this specification.
- b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1),
- c. Title, number and date of the applicable detail specification.
- d. The complete PIN of the connector or fitting ordered
- e. For category B connectors, the special tools which are to be used in the assembly of the connectors.

**6.3 Qualification.** With respect to products requiring qualification, awards will be made only for products which are at the time set for opening of bids, qualified for inclusion in the applicable Qualified Products List whether or not such products have actually been so listed by that date. The attention of the contractor is called to this requirement, and manufacturers are urged to arrange to have the products that they propose to offer to the Federal Government, tested for qualification, in order that they may be eligible to be awarded contracts or orders for the products covered by this specification. The activity responsible for the Qualified Products List is the Defense Electronics Supply Center (DESC-E), 1507 Wilmington Pike, Dayton, Ohio 45444-5000.

**6.4. References to superseded specifications.** All the requirements of MIL-PRF-39012D are interchangeable with those of MIL-C-39012C, therefore, previously existing documents (OEM drawings, etc.) referencing MIL-C-39012 need not be changed.

**6.5 Cross-reference of PIN's.** For the substitutability relationship of items covered by this specification and items covered by superseded documents, see table VIII. However, all connectors in stock may be considered interchangeable with the new PIN for a period of 1 year from the effective date of this specification.

**6.6 Engineering information.** Illustrations and additional engineering data on the connectors and fittings covered by this specification (see 3.1) are available in MIL-HBK-216, RF Transmission Lines and Fittings, copies of which are available upon request from the Naval Aviation Depot, Philadelphia, Pennsylvania.

**6.6.1 Engineering parameters.** The parameters of nominal impedance, voltage rating frequency range, and temperature range will be as specified

**6.6.2 Installation of category "B" connectors.** Field replaceable connectors for category "B" shall be those specified on the latest issue of the Qualified Products List and shall be adequate as a replacement without rework of the connector. The equipment parts list shall indicate the appropriate connector that will be used for the service replacement of a category "B" connector.

**6.7 Changes from previous issue.** The text of this specification is highlighted to indicate where changes from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the previous issue.

## MIL-PRF-39012D

TABLE VIII. Cross-reference information.

Superseded PIN M39012/	Superseding PIN M39012/	Superseded PIN M39012/	Superseding PIN M39012/
01-0001	01-0101	20-0006	20-0108
01-0002	01-0005	26-0001	26-0101
01-0003	01-0015	26-0002	26-0102
01-0004	01-0104	26-0003	26-0103
01-0025	01-0125	26-0004	26-0104
02-0001	02-0101	26-0017	26-0117
02-0002	02-0003	27-0001	27-0101
02-0004	02-0104	27-0003	27-0103
02-0005	02-0006	27-0004	27-0104
02-0031	02-0131	27-0017	27-0117
02-0001	02-0132	28-0001	28-0101
03-0001	03-0101	28-0002	28-0102
03-0002	03-0012	28-0003	28-0103
05-0001	05-0101	28-0004	28-0104
16-0001	16-0101	28-0017	28-0117
16-0002	16-0102	29-0001	29-0101
16-0003	16-0103	29-0002	29-0102
16-0011	16-0111	29-0003	29-0103
16-0018	16-0118	29-0004	29-0104
17-0001	17-0101	29-0017	29-0117
17-0002	17-0102	30-0001	30-0101
17-0003	17-0103	30-0002	30-0102
17-0011	17-0111	30-0003	30-0103
17-0018	17-0118	30-0004	30-0104
18-0001	18-0101	30-0017	30-0117
18-0002	18-0102	30-0018	30-0118
18-0003	18-0103	35-0001	35-0016
18-0011	18-0111	35-0002	35-0017
18-0018	18-0118	35-0003	35-0018
19-0001	19-0101	35-0004	35-0019
19-0002	19-0102	35-0005	35-0020
19-0010	19-0110	35-0015	35-0021
19-0011	19-0001	36-0001	36-0015
19-0018	19-0118	36-0002	36-0016
20-0001	20-0101	36-0012	36-0018

TABLE VIII. Cross-reference information - Continued.

Superseded PIN M39012/	Superseding PIN M39012/	Superseded PIN M39012/	Superseding PIN M39012/
36-0013	36-0019	59-3004	59-3009
36-0014	36-0020	59-4004	59-4009
36-0011	36-0017	59-3005	59-3010
38-0001	38-0010	59-4005	59-4010
38-0002	38-0011	UG-18E/U	01-0101
38-0009	38-0012	UG-19E/U	02-0104
39-0001	39-0101	UG-20E/U	02-0101
39-0006	39-0106	UG-21G/U	01-0005
39-0007	39-0107	UG-22F/U	02-0006
40-0001	40-0023	UG-23F/U	02-0003
40-0002	40-0024	UG-58/U	04-0002
40-0003	40-0025	UG-88/U	16-0101
40-0004	40-0026	UG-89/U	17-0101
40-0005	40-0027	UG-159D/U	03-0101
55-3001	55-3006	UG-160E/U	03-0012
55-4001	55-4006	UG-167F/U	01-0104
55-3002	55-3007	UG-204D/U	01-0015
55-4002	55-4007	UG-260/U	16-0102
55-3003	55-3008	UG-261/U	17-0102
55-4003	55-4008	UG-262/U	18-0101
55-3004	55-3009	UG-290/U	22-0001
55-4004	55-4009	UG-291/U	18-0102
55-3005	55-3010	UG-568/U	12-0001
55-4005	55-4010	UG-569/U	14-0001
56-3001	56-3006	UG-570/U	11-0002
56-4001	56-4006	UG-571/U	08-0001
56-3002	56-3007	UG-572/U	07-0001
56-4002	56-4007	UG-573C/U	06-0002
56-3003	56-3008	UG-594C/U	05-0101
56-4003	56-4008	UG-625/U	12-0001
56-3004	56-3009	UG-626C/U	06-0001
56-4004	56-4009	UG-627/U	15-0001
56-3005	56-3010	UG-629/U	08-0002
56-4005	56-4010	UG-630/U	11-0001
57-3001	57-3006	UG-631/U	09-0001
57-4001	57-4006	UG-633/U	07-0002
57-3002	57-3007	UG-680A/U	04-0001
57-4002	57-4007	UG-704/U	09-0002
57-3003	57-3008	UG-705/U	14-0002
57-4003	57-4008	UG-706/U	13-0001
57-3004	57-3009	UG-707C/U	06-0003
57-4004	57-4009	UG-708C/U	06-0005
57-3005	57-3010	UG-709/U	15-0002
57-4005	57-4010	UG-710/U	10-0001
57-3001	57-3006	UG-711C/U	06-0004
58-4001	58-4006	UG-909/U	19-0101
58-3002	58-3007	UG-910/U	19-0102
58-4002	58-4007	UG-911/U	24-0001
58-3003	58-3008	UG-912/U	24-0002
58-4003	58-4008	UG-913/U	20-0101
58-3004	58-3009	UG-935D/U	02-0032
58-4004	58-4009	UG-940C/U	02-0031
58-3005	58-3010	UG-941C/U	01-0125
58-4005	58-4010	UG-1033/U	16-0103
59-3001	59-3001	UG-1055/U	18-0103
59-4001	59-4001	UG-1056/U	17-0103
59-3002	59-3002	UG-1094/U	21-0002
59-4002	59-4002	UG-1098/U	23-0001
59-3003	59-3003	UG-1174/U	23-0002
59-4003	59-4003	UG-1185A/U	01-0005

TABLE VIII. Cross-reference information - Continued

Superseded PIN M39012/	Superseding PIN M39012/	Superseded PIN M39012/	Superseding PIN M39012/
UG-1186A/U	02-0003	UG-1767/U	09-0003
UG-1187A/U	02-0006	UG-1768/U	09-0004
UG-1392/U	44-2001	UG-1769/U	10-0002
UG-1393/U	44-2002	UG-1770/U	10-0003
UG-1394/U	48-2001	UG-1771/U	10-0004
UG-1395/U	46-2001	UG-1773/U	11-0004
UG-1396/U	46-2002	UG-1774/U	11-0005
UG-1397/U	45-2001	UG-1775/U	11-0006
UG-1398/U	45-2002	UG-1776/U	11-0007
UG-1399/U	49-2001	UG-1777/U	11-0008
UG-1460/U	73-0001	UG-1779/U	15-0003
UG-1461/U	75-0001	UG-1780/U	15-0004
UG-1462/U	74-0001	UG-1785/U	16-0004
UG-1463/U	76-0001	UG-1786/U	16-0005
UG-1464/U	77-0002	UG-1787/U	16-0006
UG-1465/U	73-0002	UG-1788/U	16-0007
UG-1466/U	75-0002	UG-1789/U	16-0008
UG-1467/U	74-0002	UG-1790/U	16-0010
UG-1468/U	76-0002	UG-1791/U	16-0009
UG-1487/U	01-0015	UG-1792/U	18-0010
UG-1533/U	47-2001	UG-1793/U	18-0009
UG-1537A/U	03-0012	UG-1794/U	17-0004
UG-1619/U	77-0001	UG-1795/U	17-0005
UG-1696/U	02-0015	UG-1796/U	17-0006
UG-1697/U	02-0016	UG-1797/U	17-0007
UG-1698/U	02-0017	UG-1798/U	17-0008
UG-1700/U	03-0004	UG-1799/U	17-0010
UG-1707/U	05-0002	UG-1800/U	17-0009
UG-1708/U	05-0003	UG-1801/U	18-0008
UG-1746/U	06-0006	UG-1802/U	18-0004
UG-1748/U	06-0007	UG-1803/U	18-0005
UG-1749/U	06-0008	UG-1804/U	19-0003
UG-1750/U	06-0009	UG-1805/U	19-0004
UG-1751/U	06-0010	UG-1806/U	19-0005
UG-1752/U	06-0011	UG-1807/U	19-0006
UG-1753/U	06-0012	UG-1808/U	19-0007
UG-1754/U	07-0003	UG-1809/U	19-0009
UG-1755/U	07-0004	UG-1810/U	19-0008
UG-1756/U	07-0005	UG-1811/U	18-0007
UG-1758/U	07-0007	UG-1812/U	20-0002
UG-1759/U	07-0008	UG-1813/U	20-0003
UG-1761/U	08-0003	UG-1814/U	18-0006
UG-1762/U	08-0004	UG-1817/U	10-0014
UG-1763/U	08-0005	UG-1819/U	03-0011
UG-1765/U	08-0007		

Hardware to connectors			
CW-123A/U	25-0006	MX-1286/U	25-0013
CW-155A/U	25-0015	MX-1142A/U	25-0001
CW-159/U	25-0016		25-0002
	25-0017	MX-1143A/U	25-0003
MX-195/U	25-0010		25-0004
CW-282/U	25-0008	MX-1144/U	25-0005
	25-0009		
	25-0011		
MX-913/U	25-0012		

## APPENDIX A

## ADDITIONAL INFORMATION ON TEST PROCEDURES

## 10. SCOPE

10.1 Scope. This appendix is to provide additional information to the user of this specification in performing the voltage standing wave ratio, RF leakage, and insertion loss tests.

20. APPLICABLE DOCUMENTS. This section is not applicable to this appendix

## 30. TEST TYPES

30.1 Voltage standing wave ratio (see 4.7.11).

30.2 Test connector. The standard test-connector interface shall be in accordance with MIL-STD-348. The standard test connector impedance shall be  $50 \pm 0.5$  ohms.

## 40. MEASUREMENTS

40.1 RF leakage (see 4.7.23).

40.1.1 Measurement technique. The measurement of the leakage from connectors is performed by collecting the leakage energy in a coaxial system surrounding the leakage source. An outline of the instrumentation is shown on figure 68. The device from which leakage is to be measured is incorporated on a uniform transmission line which is terminated in a matched load. The matched termination simplifies both the measurement procedure and data reduction. This complete coaxial system is embodied within a cylinder which forms, externally, a second coaxial system. The second coaxial system is terminated at one end in an adjustable short-circuiting plunger and at the other in a tapered transition terminated in a matched detector.

For direct leakage measurements the adjustable short circuit serves several purposes.

The short-circuit position is adjusted to assure that an adequately low impedance appears behind the equivalent leakage generator. A matched termination can be substituted, but the resulting 6-dB loss cannot be tolerated in some cases. In addition, if the leakage source is directional, as it indeed is for connectors with multiple leakage, it is possible for the leakage to be directed to this termination at some frequencies and not collected by the detector. For surface transfer-impedance measurements on connectors with leakage from more than one point in the connector, however, a matched termination is desirable in order to simplify the transformation of the measured data to absolute transfer impedance data. This is not needed to make relative comparisons in this test.

The equivalent leakage generator, in general, can have field components in the radial, axial, and circumferential\* directions. Furthermore, these components are not necessarily circularly symmetric. Locally, TE, TM, and TEM modes can all exist, and in fact, for complete leakage measurements, the detector should couple to all but the measurement is more complex in this case. The excitation of the outer coaxial line, however, is believed to be principally TEM, since the currents in the internal line are predominantly axial and symmetric. It is however, possible to have a symmetrical leakage currents which can generate the above mentioned modes. It is recommended that all measurements be made below the frequency that the higher order modes can propagate in the outer coaxial line.

The characteristic impedance of the outer coaxial line of the tri-axial system, which is formed with the inner conductor, should be matched to the detector. 50-ohm coaxial circuits are generally desired for convenience.

\* NOTE: The circumferential E field component is not usually present in axially symmetric components.

## APPENDIX A

The leakage power ratio is defined here as the ratio of the power detected to a 50-ohm detector at the output of the tri-axial unit to the power flowing through the internal 50-ohm connector or cable system. It is basically the attenuation through the tri-axial system. This definition appears arbitrary in the sense that 50 ohms is an arbitrary load impedance. However, since the leakage source impedance is comparatively low, the voltage at the detector is essentially the open circuit leakage voltage. The ratio of the input voltage to the leaky device to this output voltage is an absolute leakage quantity, as is the measured power ratio, which is identically equal to the square of this voltage ratio.

The surface transfer impedance is obtained from this ratio as follows:

The surface transfer impedance is.

$$Z_{21} = \frac{e_2}{i_1}$$

Where  $i_1$  = Current flowing in internal line and

$e_2$  = Equivalent leakage voltage in external line.

In the connector leakage case, considering the equivalent leakage generator to be  $e_2$  with an extremely low source impedance, this voltage  $e_2$  appears at detector terminals, and the adjustable short circuit assures this. For a 50-ohm transmission-line system, the input power is

$$\frac{e_2^2}{50}$$

The measured output power is:

$$\frac{e_2^2}{50} \quad (1)$$

The measured power ratio  $A^2$  is therefore,

$$A^2 = \frac{\frac{e_2^2}{50}}{\frac{e_2^2}{50}} = \frac{e_2^2}{(50)^2 i_1^2} \quad (2)$$

Substituting and by definition,

$$Z_{21} = \frac{e_2}{i_1} = 50 \text{ A} \quad (3)$$

The tri-axial system was set up principally to assess the relative leakage.

## APPENDIX A

40.1.2 Measurement procedure. In measuring the leakage power ratio,  $A^2$ , basically a substitution technique is employed. A matched detector system is installed at the output connector of the tri-axial unit, and the unit is driven as shown on figure 68. In this set-up, the short circuit is adjusted to produce a maximum indication at the detector. The detector is then connected directly to the source and the change of attenuation required to yield the initial detector level, is measured.

The sensitivity of this system is obviously limited by the sensitivity of the detector and the power available. A sensitive parallel IF substitution system is employed, and for the low leakage configuration about 100 milliwatts of power is required.

The principal sources of error are attenuator errors and mismatch at the receiver (mixer) input. For connector measurements, the error due to mismatch is directly proportional to VSWR since the equivalent leakage source impedance is small. The indicated leakage power can vary between the extremes,  $P \times VSWR$  to  $P + VSWR$ , where P is the power that would be delivered to a matched system. A VSWR of 2 will produce  $\pm 3$ -dB error therefore.

In advance of installing the inner coaxial system into the outer of the tri-axial system, the inner system may be excited, and the immediate vicinity of the leakage point or associated connector and attachment points probed with a small loop or dipole to establish how critical the mating, the connector and joints are.

#### 40.2 RF insertion loss (see 4.7.23).

##### 40.2.1 The following procedure may be used when performing the insertion loss test of 4.7.23:

Assemble one 8"  $\pm 1$ " long cable assembly terminated in a male and female test connector. Record its relative electrical length. Tune out its input VSWR using tuner number 4. Do not disturb tuner. For N, C, SC use M17/75-RG214 and "N" test connectors. For BNC, TNC, and TPS, use solid copper shield cable equivalent of M17/111-RG303 (Coaxitube number 1163.T1403-20 of Precision Tube Co.) and TNC connectors. Measure insertion loss  $L_1$  of tuner number 4 and test cable.

Insert the connector pair to be tested in the middle, remove enough so that the electrical length is the same as above within 0.05 cm, record  $\Delta l_1 + \Delta l_2$  the total length of dielectric removed; keep tuner number 4 in the same position as above. Measure insertion loss  $L_2$  of tuner number 4 and test cable including connector pair.

Measure attenuation of 50 feet of test cable and compute loss  $\alpha$  per inch  $L_c = L_2 - L_1 + \alpha (\Delta l_1 = \Delta l_2)$ .

MIL-PRF-39012D

APPENDIX B

ADDITIONAL INFORMATION ON CABLE GROUPINGS

10. SCOPE

10.1 Scope This appendix is provided to the user for additional information in determining the cable to connector combinations available. This appendix is not a mandatory part of the specification. The information contained herein is intended for guidance only.

20 APPLICABLE DOCUMENTS. This section is not applicable to this appendix.

30 CABLE GROUPINGS See notes at end of listing.

Group I

Cable M17/	Z <sub>0</sub>	F	Dielectric	Group: I
				Category: A, C
93-RG178	50	3	PTFE	*
169-00001	50	0.4	PTFE	X

Group II

Cable M17/	Z <sub>0</sub>	F	Dielectric	Group II		
				II	IIa	IIb
				Category: A	C	C
119-RG174	50	1	PE	X	X	
173-00001	50	0.4	PE	X	X	
196-00001 1/	50	1	PTFE	X	X	
113-RG316	50	3	PTFE	*	*	
172-00001	50	0.4	PTFE	X	X	
94-RG179	75	3	PTFE	X		*

1/ This cable is intended for low smoke applications.

Group III

Cable M17/	Z <sub>0</sub>	F	Dielectric	Group III
				Category: A, C
152-00001	50	12.4	PTFE	*

## APPENDIX B

Group IV

Cable M17/	Zo	F	Dielectric	Group: IV Category: A, C, D
54-RG122	50	1	PE	*
157-00001	50	0.4	PE	X
187-00001 1/	50	1	PE	X
198-00001 1/	50	0.4	PE	X

1/ This cable is intended for low smoke applications.

Group V

Cable M17/	Zo	F	Dielectric	Group: V Category: A, C, D
95-RG180	95	3	PTFE	*

Group VI

Cable M17/	Zo	F	Dielectric	Group: VI Category: A	Via C, D	Vib C, D
28-RG058	50	1	PE	X	X	
155-00001	50	0.4	PE	X	X	
183-00001 1/	50	1	PE	X	X	
197-00001 1/	50	0.4	PE	X	X	
111-RG303	50	3	PTFE	X	*	
170-00001	50	0.4	PTFE	X	X	
60-RG142	50	12.4	PTFE	X		X
158-00001	50	0.4	PTFE	X		X
84-RG223	50	12.4	PE	X		X
167-00001	50	0.4	PE	X		X
194-00001 1/	50	12.4	PE	X		X
200-00001 1/	50	0.4	PE	X		X
128-RG400	50	12.4	PTFE	*		*
175-00001	50	0.4	PTFE	X		X

1/ This cable is intended for low smoke applications

MIL-PRF-39012D

APPENDIX B

Group VII

Cable M17/	Zo	F	Dielectric	Group VII		
				Category: A	VIIa C	VIIb C
29-RG58	75	1	PE	X	X	
184-00001 1/	75	1	PE	X	X	
110-RG302	75	3	PTFE	*	*	
30-RG062	93	1	PE	X	X	
185-00001 1/	93	1	PE	X	X	
97-RG210	93	3	PTFE	X	X	
90-RG71	93	1	PE	X		*
195-00001 1/	93	1	PE	X		X

1/ This cable is intended for low smoke applications.

Group VIII

Cable M17/	Zo	F	Dielectric	Group VIII	
				Category: A, C	
2-RG6	75	3	PE	X	
180-00001 1/	75	3	PE	X	
73-RG212	50	11	PE	X	
162-00001	50	0.4	PE	X	
188-00001 1/	50	11	PE	X	
199-00001 1/	50	0.4	PE	X	
112-RG304	50	12.4	PTFE	*	
171-00001	50	0.4	PTFE	X	

1/ This cable is intended for low smoke applications.

Group IX

Cable M17/	Zo	F	Dielectric	Group IX	
				Category: A	
92-RG115	50	12.4	PTFE	*	
168-00001	50	0.4	PTFE	X	

## APPENDIX B

Group X

Cable M17/	Zo	F	Dielectric	Group:	X	Xa	Xb	Xc	Xd
				Category:	A	C, D	C, D	C	C
6-RG11	75	1	PE		X			X	
181-00001 1/	75	1	PE		X			X	
62-RG144	75	3	PTFE		X			X	
65-RG165	50	3	PTFE		X	*			
159-00001	50	0.4	PTFE		X	X			
74-RG213	50	1	PE		X	X			
189-00001 1/	50	1	PE		X	X			
163-00001	50	0.4	PE		X	X			
75-RG214	50	11	PE		X		X		
190-00001 1/	50	11	PE		X		X		
164-00001	50	0.4	PE		X		X		
86-00001	50	0.4	PTFE		X		*		
127-RG393	50	11	PTFE		*		X		
174-00001	50	0.4	PTFE		X		X		
77-RG216	75	3	PE		X				*
191-00001 1/	75	3	PE		X				X

1/ This cable is intended for low smoke applications.

Group XI

Cable M17/	Zo	F	Dielectric	Group:	XI
				Category:	A
74-RG215	50	1	PE		*
189-00002 1/	50	1	PE		X

1/ This cable is intended for low smoke applications.

Group XII

Cable M17/	Zo	F	Dielectric	Group:	XII
				Category:	A, C
78-RG217	50	3	PE		*
165-00001	50	0.4	PE		X
192-00001 1/	50	3	PE		X

1/ This cable is intended for low smoke applications

MIL-PRF-39012D

APPENDIX B

Group XIII

Cable M17/	Zo	F	Dielectric	Group: XIII Category: A
72-RG211 161-00001	50 50	1 0.4	PTFE PTFE	* X

Group XIV

Cable M17/	Zo	F	Dielectric	Group: XIV Category: A
79-RG218 166-00001 195-00001 <u>1/</u>	50 50 50	1 0.4 1	PE PE PE	* X X

1/ These cables are intended for low smoke applications

## APPENDIX B

Group XV

Cable M17/	Zo	F	OD (mm)	Dielectric	Groups.				
					XV	XVI	XVII	XVIII	XIX
129-RG401 129-00001	50 50	18 18	6.35 6.35	PTFE PTFE	X X				
130-RG402 130-00001 130-00002 130-00003 130-00004 130-00005 130-00006 130-00007	50 50 50 50 50 50 50 50	20 20 20 20 20 20 20 20	3.58 3.58 3.58 3.58 3.58 3.58 3.58 3.58	PTFE PTFE PTFE PTFE PTFE PTFE PTFE PTFE		X X X X X X X X			
133-RG405 133-00001 133-00002 133-00003 133-00004 133-00005 133-00006 133-00007 133-00008 133-00009 133-00010 133-00011	50 50 50 50 50 50 50 50 50 50 50 50	20 20 20 20 20 20 20 20 20 20 20 20	2.18 2.18 2.18 2.18 2.18 2.18 2.18 2.18 2.18 2.18 2.18 2.18	PTFE PTFE PTFE PTFE PTFE PTFE PTFE PTFE PTFE PTFE PTFE PTFE			X X X X X X X X X X X X		
151-00001 151-00002	50 50	20 20	1.19 1.19	PTFE PTFE				X X	
154-00001 154-00002	50 50	20 20	0.86 0.86	PTFE PTFE					X X

mm	Inches
0.86	.034
1.19	.047
2.18	.086
3.58	.141
6.35	.250

## NOTES:

1. Zo denotes nominal impedance in ohms.
2. F denotes the upper frequency limit in GHz. For cables with 0.4, the structural return loss and the power handling capability are not specified. Attenuation is tested only at 0.4 GHz
3. PE denotes a polyethylene dielectric PTFE denotes a polytetrafluoroethylene dielectric
4. Dimensions are in millimeters Inch-pound equivalents are given for information only
5. \* denotes preferred cable

MIL-PRF-39012D

CONCLUDING MATERIAL

Custodians:

Army - CR  
Navy - EC  
Air Force - 85  
NASA - NA

Preparing activity:  
DLA - ES

(Project 5935-4004)

Review activities:

Army - AR, AT, MI  
Navy - AS, MC, OS, SH  
Air Force - 19, 99

# STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

## INSTRUCTIONS

- 1 The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
- 2 The submitter of this form must complete blocks 4, 5, 6, and 7.
- 3 The preparing activity must provide a reply within 30 days from receipt of the form.

**NOTE:** This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

<b>I RECOMMEND A CHANGE:</b>	1 DOCUMENT NUMBER MIL-PRF-39012 D	2 DOCUMENT DATE (YYMMDD) 950713
3. DOCUMENT TITLE CONNECTORS, COAXIAL, RADIOFREQUENCY, GENERAL SPECIFICATION FOR		
4 NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed)		
5. REASON FOR RECOMMENDATION		
6. SUBMITTER		
a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (if applicable)	7. DATE SUBMITTED (YYMMDD)
8. PREPARING ACTIVITY		
a. NAME DEFENSE ELECTRONIC SUPPLY CENTER	b. TELEPHONE (Include Area Code) (1) Commercial (513) 296-5391 (2) AUTOVON 986-5391	
c. ADDRESS (Include Zip Code) ATTN DESL-ELDI 1507 WILMINGTON PIKE DAYTON OH 45444-5765	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT Defense Quality and Standardization Office 5203 Leesburg Pike Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340	